BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No. RRND/EE/Ten/15/2016-17, Date: 23.09.2016

E-procurement No: BBMP/2015-16/RD/WORK_INDENT20539/CALL-4

SCHEDULE -B

Name of Work : Construction and laying of new pipeline works and cistern (MWS) for existing and new borewells in ward no 16

Sl.No	Qty	Description of work	Unit	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	1182.60	Earthwork excavation for the foundations of the buildings,water supply,sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of the pits and trenches,stacking the excavated soil clear from the excavations with lead upto 50m after breaking of clod complete a per specifications.	sqm	270.0	Rupees Two Hundred Seventy Only
2	2190.00	Provding and fixing to wall, celing and floor nigh density polythlene pipes 6.00 kg/sq cm working pressure 63mm outside diameter with special flange, compression type fitting, wall, clips, making good the wall ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications.	rmt	350.0	Rupees Three Hundred Fifty Only
3	1182.60	Refilling earth around pipe lines, cables in layers not exceeding 520 cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5 m including cost of all labour complete as per specifications	cum	70.0	Rupees Seventy Only

Signature of the contratror

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner